BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

APPROVED SCHEDULE –'B'

Name of Work:- Improvements and Development of roads and drains in ward no:02 Chowdeshwari ward, Yelahanka sub division

Sl	Description	Unit	Approved Qty	Approved Rate Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate in Words
1	KSRRB200-8: Clearing and grubbing road land including uprooting rank vegetation, grass, brush, shrubs, saplings and trees of girth upto 300mm by manual means in area of light hungle removal of stumps disposal of unserviceable material, stacking of serviceable materials labours charges complete as per specifications MORTH/ Chapter 2 (KPWD ST 2018-19)	Sqm	900.00	10.60	Rupees ten and paise sixty Only
2	KSRRB 300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications. MORTH/ Chapter 3 complete as per specifications and directions of the Engineer in charge.	Cum	1107.36	207.60	Rupees Two hundred seven and paise sixty Only
3	KSRRB M100-6 Crushing of stone boulders of 150 mm size in an intergrated stone crushing unit of 200 tonners per hour capacity comprising of primary and secondary crushing units belt conveyour and vibrating screens to obtain stone aggreagates of 13.2 mm nominal size including cost of materials equipments labour etc., complete MORTH-100 chapet 1 (KPWD SR 2018-19)	Cum	126.00	845.88	Rupees Eight hundred forty five and paise eighty eight Only
4	KSRB 4.1.2 Providing and laying in position plain cement concree of Mix 1:3:6 with OPC @ 220kgs with 40mm and down size graded granite metal coarse aggregate @ 0.892 cum and fine aggregates @ 0.465cum machine mixed machine mixed concree laid in layers not exceeding 15 cum thick, well compacted in foundation including cost of all materials labour HOM curring complete as per specifications specification No.KBS 4.1, 4.2 (KPWD SR 2018-19)	Cum	421.02	5505.64	Rupees Five thousand five hundred five and paise sixty four Only

Executive Engineer-3
KRIDL, BBMP, Bangalore

Sl	Description	Unit	Approved Qty	Approved Rate Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate in Words
5	KSRB 4.2.2 Providing and laying in position reinforced dement concrete of Desig mix M20 with OPC @ 320kgs with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.460cum with super plasticisers @ 3 liters cinfirming to IS 9103-1999 reafirmed 2008 machine mixed concete laid in layers not exeeding 15cms thick, vibrated for all works in founation for footings pedastal retainin walls return walls , walls (any tthickness) including atached pilasters columnspillars posts struts buttersses bed blocks anchor blocks & plinths etc., including cost of all materials labour HOM curing complee but excluding cost of reinforcement as per specifications . specification No KBS 41. 4.6 (KPWD SR 2018-19)	Cum	135.00	5998.54	Rupees Five thousand nine hundred ninety eight and paise fifty four Only
6	KSRB 4.6.4 providing and removing centering shutering strutting propping etc., and removal of form work for vertical surface such as walls at any thickness including attached pilaters butttressess plinth cills and string courses cost of all materials laour complete as per specification. specification No KBS 4.6.2 (KPWD SR 2018-19)	Sqm	1170.00	379.48	Rupees Three hundred seventy nine and paise forty eight Only
7	KSRB 4.9.2 Providing T.M.T steel reinrcement for R.C.C work including sraightenung cutting bending hookin placing in position lapping and/or welding wherever required tying with binding wire and anchoring to the adjoining members wherever necessar complee as per design (Laps, hooks and wastage shall not be measured and paid) cost of materials labour HOM complete as per specificaions specification No KBS 4.6.3 Do TMT bars fe 500 (KPWD SR 2018-19	Tonne	8.78	75223.96	Rupees Seventy five thousand two hundred twenty three and paise ninety six Only
8	Providing precast slab of 1oo mm thick including cost of all materials lbour curing transportion loading unloading etc., complete as per the direction of engineer in charge Data rate	sqm	360.00	2337.00	Rupees Two thousand three hundred thiety seven Only

Executive Engineer-3
KRIDL, BBMP, Bangalore

Sl	Description	Unit	Approved Qty	Approved Rate Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate in Words
9	Providing and fixing pre cast slolid cement concrete kerb stones made our of C.C 1.2.4 with top and bottom width 114 and a65 mm respectively 400mm high and 450 mm in length finised witth CM 1:3 plastering and finising cutting including from work curing including cost of all materials labour hire charges of machinery loading unloadng lead and lift transportation etc complete (KPWD SR 2018-19	Nos	873.00	432.48	Rupees four hundred thirty two and paise forty eight Only
10	KSRB 14.6 Providing and laying heavy duty cobble stone 60mm thick interlock pavers using cement and course sand for manufacture of blocks of approved size shape and colour with a minimum compressive strength of 281kg per sqm over 50mm thick sand bed average thickness and comacting with plae vibrato having 3 tons compaction force therby forcing part of sand underneath to come up in between joints final compaction of paver surface joints into its final level including cost of materials labour and HOM complete as per specification. specification (KPWD SR 2018-19	sqm	2386.80	1116.18	Rupees one thousand one hundred sixteen and paise eighteen Only

Signature of the Contractor

Executive Engineer-3
KRIDL, BBMP, Bangalore

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.